

947 -X

A DOG 4750

U. S. ARMY

61


Technical Note 2-68

AIRCRAFT INSTRUMENT PANEL PLACEMENT

John A. Barnes

January 1968

HUMAN ENGINEERING LABORATORIES



ABERDEEN PROVING GROUND,
MARYLAND

This document has been approved for public
release and sale; its distribution is unlimited.

20030113080

947

947

Destroy this report when no longer needed.
Do not return it to the originator.

The findings in this report are not to be construed as an official Department of the Army position unless so designated by other authorized documents.

Use of trade names in this report does not constitute an official endorsement or approval of the use of such commercial products.

AIRCRAFT INSTRUMENT PANEL PLACEMENT

John A. Barnes

January 1968

APPROVED:

A handwritten signature in dark ink, appearing to read "John D. Weisz", is written over a horizontal line.

JOHN D. WEISZ

Technical Director

Human Engineering Laboratories

U. S. ARMY HUMAN ENGINEERING LABORATORIES
Aberdeen Proving Ground, Maryland

ABSTRACT

The placement of the aircraft instrument panel has been governed by the 1947 recommendations of the Armed Forces-NRC Vision Committee. This distance, 28 inches from eye to panel, is not always compatible with present-day aircraft designs. A method for determining the placement of the instrument panel is developed and the maximum allowable eye-to-panel distance is given in this paper.

CONTENTS

ABSTRACT	iii
INTRODUCTION.	1
VISUAL FACTORS	1
ANTHROPOMETRIC FACTORS	7
EVALUATION OF FACTORS	7
CONCLUSIONS	10
REFERENCES	11

FIGURES

1. Distribution of Panel Viewing Distance Settings: All Subjects, All Trials. Based on 560 Individual Settings	2
2. Probability of Detection as a Function of the Visual Angle Given Constant Illumination and Target Size	3
3. Viewing Distance as a Function of Letter Height Given a Constant 30 FL Luminance Level	6
4. Instrument Panel, Maximum Placement	9

TABLES

1. Constant Letter Height and Stroke Width	4
2. Constant Visual Angle	5
3. Relationship Between Illumination and Visual Acuity	8

AIRCRAFT INSTRUMENT PANEL PLACEMENT

INTRODUCTION

The placement of an aircraft instrument panel appears to be a simple matter. Military standards describe the field of vision required for the various types of aircraft, measures are available which anthropometrically describe the population that will use the aircraft, and much experimental data has been published concerning letter heights, stroke widths, viewing distances for various illumination levels, and optimal meter size. In the past, instrument panels have been placed so that the eye-to-panel distance was 28 inches. This was the distance recommended as a standard by the Armed Forces-NRC Vision Committee in 1947. The modern aircraft, especially light-weight rotary-wing types, cannot readily conform to this recommended distance.

This paper will present the various limiting factors concerning instrument panel placement and will recommend a method of determining the most economical envelope of instrument panel placements.

VISUAL FACTORS

A study by Obermayer and Muckler shows a mean preferred eye-to-panel or viewing distance of 29.19 inches with over half of the mean preferences falling in a three-inch range (27.63 to 30.55 inches). Figure 1 displays these results.

While preference is a minor design criterion, it is a factor for consideration. A more important factor in determining design is efficiency in use. Thus, for the aircraft instrument panel, the ease with which various indicators may be read is important. The conditions considered here were those specified by several publications; e.g., The Human Engineering Guide to Equipment Design, MIL-STD- 803A-1 (USAF), and Vision and Visual Perception. For low levels of illumination (.1 foot-candle), the minimal letter/figure height for critical markings was given as .15 inch with a stroke width of .019 inch (1/8 of the letter/figure height). These dimensions were verified for this paper by measuring the markings on actual aircraft instruments.




Fig. 1. DISTRIBUTION OF PANEL VIEWING DISTANCE SETTINGS: ALL SUBJECTS, ALL TRIALS. BASED ON 560 INDIVIDUAL SETTINGS

Given constant illumination and contrast, detectability and legibility are determined by the visual angle subtended by the letters or figures. Indicator figure detectability is required 100 percent of the time. Detection probability as a function of visual angle is given in Figure 2. This graph shows that a visual angle of 1.6 minutes or greater is required for 100 percent detectability. The visual angle is determined by the following formula: $\theta = 2 \text{ arc tan } X/2D$ where X is the letter height or stroke width and D is the eye-to-panel distance. Table 1 gives the visual angle and acuity values for a .15-inch letter height with a stroke width of .019 inch for an eye-to-panel range of 24 to 40 inches. The acuity value is computed as $1/\text{Visual Angle}$ expressed in minutes of arc.




Fig. 2. PROBABILITY OF DETECTION AS A FUNCTION OF THE VISUAL ANGLE
GIVEN CONSTANT ILLUMINATION AND TARGET SIZE

TABLE 1

Constant Letter Height and Stroke Width

Constants: .15 inch Letter Height .019 inch Stroke Width			
View Distance (Inches)	Visual Angle H (Minutes)	Visual Angle W (Minutes)	Acuity W
24	21.50	2.68	.3721
25	20.62	2.57	.3883
26	19.80	2.47	.4040
27	19.10	2.37	.4188
28	18.40	2.30	.4386
29	17.72	2.21	.4520
30	17.16	2.16	.4651
31	16.62	2.10	.4819
32	16.13	2.02	.4969
33	15.62	1.93	.5128
34	15.16	1.88	.5263
35	14.72	1.83	.5442
36	14.32	1.75	.5594
37	13.88	1.72	.5755
38	13.55	1.70	.5882
39	13.23	1.63	.6060
40	12.85	1.60	.6201

TABLE 2

Constant Visual Angle

Constant Angle: 18' 24"		
Panel Distance (Inches)	Letter Height (Inches)	Stroke Width (Inches)
24	.129	.016
25	.134	.017
26	.140	.017
27	.145	.018
28	.150	.019
29	.156	.020
30	.161	.020
31	.167	.021
32	.172	.022
33	.177	.022
34	.183	.023
35	.188	.024
36	.194	.024
37	.199	.025
38	.204	.026
39	.210	.026
40	.215	.027




Fig. 3. VIEWING DISTANCE AS A FUNCTION OF LETTER HEIGHT
GIVEN A CONSTANT 30 FL LUMINANCE LEVEL

In Table 2 the visual angle is held constant and the letter height and stroke width are varied to show the change necessary to maintain a constant visibility throughout the given distance range.

A study by Murrell et al using Royal Navy men with 20/20 vision and luminance levels of 30 foot-lamberts reported that a visual angle of two minutes of arc gave the optimal percentage of correct readings and speed of reading. Two minutes of arc is also recommended by Platonov. The relationship of letter height and reading distance as reported by Murrell et al is shown in Figure 3.

Luminance level or level of illumination is a critical factor in determining letter size. If the letter size is fixed and the requirement for 20/20 acuity is maintained, then the minimum level of illumination must be specified. Table 3 from Tscherning shows the relationship between illumination and visual acuity. It can be readily seen that an illumination value of .139 foot-candles is necessary for an acuity of 20/20.

ANTHROPOMETRIC FACTORS

One other factor in panel placement is the physical size of the aviator. The instrument panel must be placed so that the 1st-percentile aviator can reach the panel. The Anthropometry of Naval Aviators (NAEC-ACEL-533), the Anthropometry of Army Aviators (TR EP-150), and the Anthropometry of Flying Personnel (WADC-TR 52-321) were used to determine the size of the 1st and 99th percentile men for this study, but none of these publications contains one necessary measurement, the aviator's maximum functional reach when restrained by a lap belt. This measure is basically the maximum arm reach upwards (as given in TR EP-150) rotated about the Seat Reference Point (SRP) and converted to functional reach. A study now in progress at the U. S. Army Human Engineering Laboratories furnished this measure, 46 inches for the 1st-percentile Army aviator. This was the value for maximum functional reach when restrained by a lap belt that was used in this paper. This measure was considered to extend from the SRP to the top of the instrument panel. Data presented in WADC TR 56-171 verified this value.

EVALUATION OF FACTORS

From Figure 1 the preferred eye-to-panel distance determined from 560 trials is 29.19 inches. These judgments were made by pilots and non-pilots. Figure 2 shows that visual angles in excess of 1.6 minutes of arc are required for 100 percent detectability. Table 1 shows that for a eye-to-panel distance of 40 inches the visual angle for stroke width, the critical measurement in letter recognition, is equal to the minimum value that is required for 100 percent detectability. Table 3 verifies the minimum illumination of .1 foot-candle as the requirement for 20/20 acuity. The physical size of the aviator also determines the placement of the instrument panel as well as his visual abilities.

A survey of pilots now flying helicopters was conducted to determine if vibration should be considered as a factor in this paper. It was the unanimous opinion of these pilots that vibration did not affect their ability to read any of the instruments.

TABLE 3

Relationship Between Illumination and Visual Acuity

Illumination		Acuity	Snellen
Meter-Candles	Foot-Candles		
.016	.0015	.075	20/267
.020	.0019	.150	20/134
.028	.0026	.210	20/96
.047	.0044	.300	20/67
.120	.01110	.370	20/54
.250	.0230	.500	20/40
.670	.0620	.750	20/27
1.500	.1390	1.000	20/20
16.700	1.5520	1.250	20/16
5400.000	501.7000	1.500	20/13




Fig. 4. INSTRUMENT PANEL, MAXIMUM PLACEMENT

Figure 4 illustrates the results of the evaluation of the factors discussed in this paper. The following are the factors:

1. Illumination levels of .1 foot-candles or greater.
2. Figure heights of .15 inches.
3. Stroke widths of .019 inches, 1/8 of letter height.
4. A 1st percentile maximum functional reach.
5. A 99th percentile Eye Reference Point (ERP).
6. A 10-inch seat height.
7. A 30-inch top of panel height.
8. Panel Reference Point (PRP) at 5 inches from panel top.

CONCLUSIONS

If the present indicator sizes, visibilities, and detection probabilities are to be maintained, aircraft instrument-panel viewing distances in excess of 38 inches are not permissible unless degradation of visual and operational capabilities below the 100 percent level can be justified.

REFERENCES

1. Baker, C. A. & Grether, W. F. Visual presentation of information. WADC-TR-54-160, Aero Medical Lab., Wright Air Development Center, Wright-Patterson AFB, Ohio, 1954.
2. Brown, F. R. The effect of stroke-width and form upon legibility of numerals. TED-NAMEL-609-4, Naval Air Material Center, Philadelphia, Pa., 1953.
3. Ely, J. H. et al. Layout of workplaces. WADC-TR-56-171, Aero Medical Lab., Wright Air Development Center, Wright-Patterson AFB, Ohio, 1956.
4. Graham, C. H. (Ed.) Vision and visual perception. New York: John Wiley & Sons, 1965.
5. Morgan, C. T., Cook, J. S., Chapanis, C., & Lund, M. Human engineering guide to equipment design. New York: McGraw-Hill, 1963.
6. Murrell, K. F. H., Laurie, W. D., & McCarthy, C. The relationship between dial size, reading distance and reading accuracy. Ergonomics, 1958, 1, 2, 182.
7. Obermayer, R. W., & Muckler, F. A. Preferences for instrument panel viewing distance. J. Eng. Psychol., 1962, 1, 4, 141.
8. Platonov, K. K. Voennoye izdatel'stvo, Ministerstva Oborony Soyuza SSR, Moscow. Aviation Psychology, 1960.
9. Stevens, S. S. Handbook of experimental psychology. New York: John Wiley & Sons, 1951.
10. Tscherning, M. Physiologic optics. The Keystone, Philadelphia, Pa., 1904.

DISTRIBUTION LIST

<p>Hq, USA Materiel Command, Wash, DC AMCRL(Dr. Thomas, Ofc Res & Labs) 1 AMCRD (Air Def & Msl Ofc) 1 AMCRD (Air Mobility Ofc) 1 AMCRD (Comm-Elec Ofc) 1 AMCRD (Ground Mobility Ofc) 1 AMCRD (Weapons Ofc) 1 AMCRD-TE (Dr. Borum) 1 USA Materiel Command Board Bldg 3072, APG 1</p> <p>Pres, USA Maintenance Board AMXMB-EME, Fort Knox, Ky. 1</p> <p>USA Test & Eval Command Bldg 3071, APG 1</p> <p>Dr. J. E. Uhlaner, Dir, Res Labs USA Behavioral Science Rsch Lab Washington, D. C. 1</p> <p>USA Behavioral Science Rsch Lab Washington, D. C. 1</p> <p>Behavioral & Social Science Res Div Ofc, Chief of Res & Development, DA Washington, D. C. 1</p> <p>CO, USA Res Ofc, Box CM Duke Station, Durham, N. C. 1</p> <p>Deputy Chief of Staff for Personnel Dept of Army, Wash, D. C. Personnel Res Div 1</p> <p>CG, USA Mobility Equip R&D Labs. Fort Belvoir, Va. Tech Document Center 1 Human Factors Branch 1 STINFO Branch 2</p> <p>Combat Opns Res Gp Test & Exper Br, PO Box 116 Fort Belvoir, Va. Dr. Emmoran B. Cobb 1</p> <p>CG, USACDC, Ft Belvoir, Va. CDCCD-C 1 CDCMR 1 CDCRE 1</p> <p>CO, USACDC Special Warfare Agency Fort Bragg, N. C. 1</p> <p>CO, USACDC Avn Agency Fort Rucker, Ala. 1</p> <p>CO, USACDC Engineer Agency Fort Belvoir, Va. 1</p> <p>CO, USACDC CBR Agency Fort McClellan, Ala. 1</p> <p>CO, USACDC Comm-Electr Agency Fort Monmouth, N. J. 1</p>	<p>CO, USACDC Transportation Agency Fort Eustis, Va. 1</p> <p>CO, USACDC Infantry Agency Fort Benning, Ga. 1</p> <p>CO, USACDC Air Def Agency Fort Bliss, Texas 1</p> <p>USACDC Liaison Office Bldg 3071, APG 1</p> <p>CG, USACDC Combat Arms Group Fort Leavenworth, Kan. 1</p> <p>USACDC Experimentation Command Fort Ord, Calif. Liaison Office 1 Tech Libr, Box 22 1</p> <p>Plans Officer (Psychologist) G-3/2 Section Hqs, USACDCEC Fort Ord, Calif. 1</p> <p>CG, USACDC Combat Serv Support Grp, Fort Lee, Va. 1</p> <p>CO, USACDC Maint Agency, APG 1</p> <p>CO, USACDC Artillery Agency Fort Sill, Okla. 1</p> <p>CO, USACDC Armor Agency Fort Knox, Ky. 1</p> <p>CO, USACDC Med Serv Agency Fort Sam Houston, Texas 1</p> <p>CO, USACDC Military Police Agency Fort Gordon, Ga. 1</p> <p>CO, USACDC Supply Agency Fort Lee, Va. 1</p> <p>Director of Research HumRRO Div No. 5 (Air Defense) PO Box 6021, Fort Bliss, Texas 1</p> <p>USA Armor, Human Res Unit Fort Knox, Ky. 1 Library 1</p> <p>CO, USA Med Res Lab, Ft Knox 1</p> <p>Commandant, Army Logistics Mgmt Ctr, Fort Lee, Va. E. F. Neff, Proc Div 1</p> <p>Dir Res, USA Avn HRU PO Box 428, Fort Rucker, Ala. Librarian 1</p> <p>Commandant, USA Artillery & Missile School, Fort Sill, Okla. Dir, Dept of Gunnery 2 USAAMS Tech Library 1</p>	<p>Hq, USA Tank-Automotive Command Warren, Mich. SMOTA-RR 1 SMOTA-RTS.1 1</p> <p>Hq, USA Detroit Arsenal Warren, Mich. SMOTA-RCEC 1</p> <p>CG, USA Weapons Command Rock Island Arsenal, Ill. AMSWE-RDT 1 AMSWE-SMM-P 1 SWERI-RDD-PD 2</p> <p>CO, USA Med Equip Res & Dev Lab Fort Totten, Flushing, LI, N. Y. 1</p> <p>CO, Yuma Proving Ground Yuma, Ariz. Tech Library 1</p> <p>CG, USA Electronics Command Fort Monmouth, N. J. AMSEL-RD-GDA 1</p> <p>CG, USA Elec Proving Ground Fort Huachuca, Ariz. Tech Info Center 1 Jeff Abraham, Test Directorate 1</p> <p>CG, US CONARC, Fort Monroe, Va. 1 ATTIT-RD-RD 1</p> <p>CO, Harry Diamond Laboratories Washington, D. C. AMXDO-EDC (B. I. Green) 1</p> <p>CO, USA Edgewood Arsenal Human Factors Br 1 Psychology Br 1 Env Hyg Agency Library 2</p> <p>CO, Frankford Arsenal, Phila, Pa. SMUFA-N/6400/202-4 (HF) 1 Library (C2500, BI 51-2) 1</p> <p>CO, Picatinny Arsenal, Dover, N. J. SMUPA-VC1 (Dr. Strauss) 1</p> <p>Libr, George Washington Univ. HumRRO, Alexandria, Va. 1</p> <p>CO, USA Res Inst of Environ Med Natick, Mass. MEDRI-CL (Dr. Dusek) 1</p> <p>Dir, Walter Reed Army Inst Res Washington, D. C. Neuropsychiatry Div 1</p> <p>CG, USA Missile Command Redstone Arsenal, Ala. AMSMI-RBLD 1 AMSMI-RHP (Chaikin) 1</p>
---	--	--

President USA Infantry Bd Ft Benning, Ga	1		Mr. George Ganem, Itek Corp. 10 Maguire Rd. Lexington, Mass	1
CO, Watervliet Arsenal, N. Y.		6570 AMRL (MRHE)	2 Research Analysis Corp	
SWEWV-RDT	1	6570 AMRL (MRHER/Bates)	1 McLean, Va.	
USAETL-TSB Fort Belvoir, Va. T. L. Fick	1	6570 AMRL (MRHE/Warrick) Wright-Patterson AFB Ohio	1 Doc Libr	1
Dr. Kurke, Tech Opns, Inc. 1901 Ft Myer Dr, Arlington, Va.	1	Electronic Sys Div (AFSC) Scientific & Tech Info Div (ESTI) L. G. Hanscom Field, Bedford, Mass	Ritchie, Inc., Dayton, Ohio	1
CG, White Sands Msl Range White Sands Missile Range, N. M. Technical Library STEWs-TE-Q (Mr. Courtney) STEWs-LG-VT (Tech Libr)	1 1 1 1	Civil Aeromedical Institute Fed Avn Agency Aero Ctr PO Box 25082, Okla City, Okla Psychol Br, AC-118	Libr, Chrysler Def Engr, Detroit	1
USA Genl Equip Test Activity Methods Engr Dir Hum Factors Fort Lee, Va.	1	Defense Documentation Center Cameron Station, Alexandria, Va.	Mr. Wesley Woodson, Man Factors, Inc., San Diego, Calif.	1
USA Tropic Test Ctr, PO Drwr 942 Ft Clayton, Canal Zone Behavioral Scientist	2	US Dept Commerce, CFSTI Sills Bldg, Springfield, Va.	Dr. Herbert J. Bauer GM Rsch Labs, GM Tech Ctr Warren, Mich.	1
USA Arctic Test Ctr, R&D Ofc APO Seattle, Wash (Alaska) Mr. B. Jacobson	1	USPO Dept, Bur Res & Engr 7900 Wis Ave, Bethesda, Md. Mr. D. Cornog	AC Electronics Div, GMC Milwaukee, Wis. Tech Libr Dept 32-55 G. J. Ferwerda, Hum Factors	1 1
Dir, Military Psychol & Leadership US Military Academy, West Point, NY	1	Ctr for Research in Social Systems The American University Washington, D. C.	Dir, Human Factors Engineering Mil Veh Org, GMC Tech Center, Warren, Mich.	1
Tech Libr, Bldg 313, APG	1	Dr. Richard A. Wunderlich Psychol Dept, Catholic Univ Washington, D. C.	Hughes Aircraft Co, Tech Doc Ctr Culver City, Calif.	1
Tech Libr, Br 3, D&PS, Bldg 400	1	Serials Unit, Purdue Univ Lafayette, Ind.	Engineering Library	1
CO & Dir, Naval Training Dev Ctr Orlando, Fla.	1	Dr. F. Loren Smith Dept Psychol, Univ Delaware Newark, Del.	Mr. Henry E. Guttman Sandia Corp., Albuquerque, N. M.	1
Hq, USA Medical R&D Command Main Navy Bldg, Wash, D. C. Behavioral Sciences Rsch Br	1	Dir, Hum Engr Info & Analysis Serv Systems Bldg, Tufts University Medford, Mass.	Mr. Robert F. Roser, HF, Sys Eng General Dynamics Pomona Bx 2507, Pomona, Calif.	1
Dir., Naval Research Laboratory Washington, D. C. Code 5120 Code 5143A	1 1	Dr. Leonard Uhr Computer Sci Dept, Univ Wisconsin 1210 Dayton St., Madison, Wis.	Mgr, Behavioral Sciences Litton Scientific Support Lab Fort Ord, Calif.	1
Code 455 Ofc of Naval Research Washington, D. C. Engr Psychol Br (Mr. Farr)	2 1	Amer Inst for Research 8555 16th St., Silver Spring, Md. Library	Sprint Human Factors MP 537 Martin Co., Orlando, Fla.	1
US Navy Electronics Laboratory San Diego, Calif Ch, Human Factors Div	1	Amer Inst for Research 135 North Bellefield, Pgh., Pa. Library	Psychological Abstracts 1200 17th St., N. W. Washington, D. C.	1
US Navy Liaison Ofc, Bldg 400, APG	1	Amer Inst for Research PO Bx 1113, Palo Alto, Calif. Library	Dr. Cohen, HF Dept, Link Group General Precision, Inc. Binghamton, N. Y.	1
Dr. Martin Tolcott, Ctr for Nav Anal Inst of Naval Studies, Wilson Blvd Arlington, Va.	1	Inst for Defense Analyses Arlington, Va., Dr. J. Orlansky	Mr. Brome, JFK Mem Library Calif State College at LA, Calif.	1
Dr. Morgan Upton Aerospace Med Res Dept US Naval Air Dev Ctr, Johnsville, Pa.	1	The Franklin Inst Research Labs Philadelphia, Pa. (Tech Rept Libr)	Dr. Stoudt, School of Public Health Harvard Univ, Boston, Mass.	1
US Marine Liaison Ofc, Bldg 3071	1	Dept Psychol, Univ of Maryland College Park, Md.	Dr. Pearson, Dept Industrial Engr NC State Univ, Raleigh, N.C.	1
RAIDC (EMEDI) Griffiss AFB, N. Y.	1		Dr. Seidenstein, Lockheed Msl & Space Co., Sunnyvale, Calif.	1
AFSC STLO, Bldg 390, APG	1		Mr. James Moreland, R&D Ctr Westinghouse Elec Corp. Pittsburgh, Pa.	1
AMD (AMRH) Brooks AFB, Texas	1		Grumman Acft Engr Corp Bethpage, LI, N. Y. Leo Bricker, Life Scientist Plant 5	1

Unclassified
Security Classification

DOCUMENT CONTROL DATA - R & D

(Security classification of title, body of abstract and indexing annotation must be entered when the overall report is classified)

1. ORIGINATING ACTIVITY (Corporate author) U. S. Army Human Engineering Laboratories Aberdeen Proving Ground, Maryland 21005		2a. REPORT SECURITY CLASSIFICATION Unclassified	
		2b. GROUP	
3. REPORT TITLE AIRCRAFT INSTRUMENT PANEL PLACEMENT			
4. DESCRIPTIVE NOTES (Type of report and inclusive dates)			
5. AUTHOR(S) (First name, middle initial, last name) John A. Barnes			
6. REPORT DATE January 1968		7a. TOTAL NO. OF PAGES 16	7b. NO. OF REFS 10
8a. CONTRACT OR GRANT NO.		9a. ORIGINATOR'S REPORT NUMBER(S)	
b. PROJECT NO.			
c.		9b. OTHER REPORT NO(S) (Any other numbers that may be assigned this report)	
d.			
10. DISTRIBUTION STATEMENT This document has been approved for public release and sale; its distribution is unlimited. Released to Department of Commerce for sale to the public.			
11. SUPPLEMENTARY NOTES		12. SPONSORING MILITARY ACTIVITY	
13. ABSTRACT The placement of the aircraft instrument panel has been governed by the 1947 recommendations of the Armed Forces-NRC Vision Committee. This distance, 28 inches from eye to panel, is not always compatible with present-day aircraft designs. A criterion for determining the placement of the instrument panel is developed and the maximum allowable eye-to-panel distance is given in this paper.			

14. KEY WORDS	LINK A		LINK B		LINK C	
	ROLE	WT	ROLE	WT	ROLE	WT
Placement of Aircraft Instrument Panel Eye-to-Panel Distance Human Factors Engineering						